




Second Floor Plan Showing Roof Support Structure

1:50

LEGEND:

- New brickwork wall formed from clay bricks to BS EN 711-1 with a compressive strength of 20N/mm² and durability designation FN or FL in class (iii)/M4 mortar.
102.5mm thick unless noted otherwise.
- 100mm thk (u.n.o) Aircrete blockwork wall
3.6N/mm² minimum compressive strength in Class M4 mortar (u.n.o)
- 140 / 215mm thk (u.n.o) Aggregate concrete blockwork wall
7.3N/mm² minimum compressive strength in Class M4 mortar (u.n.o)
- 140 / 215mm thk (u.n.o) Aggregate concrete blockwork wall
10.4N/mm² minimum compressive strength in Class M4 mortar (u.n.o)
- MJ - Masonry Movement Joint
- Load Bearing / Ply Sheathed Stud Wall
Studs to be min 47x100dp @ 400 crs with
12mm plywood to be fixed to one side of the internal stud wall, either 3mmØ nails or 4.5mmØ screws, 50mm long @ 150mm around perimeter of ply and 300 crs internally

- Walls / structure above
30x5 MS straps @ max 2m crs fixed to min 3No joists/rafters and bent into cavity. Solid noggins to be provided at straps location.
- PCC Planks
Precast hollowcore slabs to specialists design
- Flat Roof
engineered joists
Metal web (eco) joists to specialist manufacturer details. Assumed 75x253mm dp @ 400mm ctrs. Note. Max 124mm Ø, 115mm square or 180x100mm dp rectangular services can fit through web
- Rafters 1
min 47x200dp C16 rafters @ 400 crs
Double up rafters around opening
- Flat Roof 1
engineered joists
Metal web (eco) joists to specialist manufacturer details. Assumed 225mm dp @ 400mm ctrs. Note. Max 124mm Ø, 115mm square or 180x100mm dp rectangular services can fit through web
- Dormer Rafters 1
min 2No 47x200dp C16 rafters bolted together with M10 Grade 8.8 bolts @ 450mm staggered ctrs
- Diagonal Brace
47x150dp C16 @ 1200mm ctrs
- Rafters 2
min 47x200dp C16 rafters @ 400 crs
Double up rafters around opening
- Flat Roof 2
47x200mm dp C16 flat roof joists @ 400mm ctrs.
- Dormer Rafters 2
min 2No 47x200dp C16 rafters bolted together with M10 Grade 8.8 bolts @ 450mm staggered ctrs
- Hip Rafters
min 2No 47x200dp C16 rafters with 200x8mm thk S275 plate bolted between with M10 Grade 8.8 bolts @ 450mm staggered ctrs & 4No bolts at bearings

Engineered joists and PCC Planks are to be designed by a specialist manufacturers. PRP to be provided with calculations and drawings at least 2 weeks prior to fabrication.

Lintel Key		
Type	Product reference / Material	Min Endbearing Length
L1	Stressline 140x140 dp PCC lintel (or similar) or IG Box 140	150
L2	100x140dp Stressline R15A PCC lintel (or similar) or IG Box 100	150
L3	Outer Leaf: IG L11 Inner Leaf: Stressline RW22A 140x215 dp PCC lintel (or similar) or IG HD Box 140	150
L4	Outer Leaf: IG L11 Inner Leaf: 140x140x5 SHS Beam	150
L5	IG L11HD 150 WIL	150
L6	IG L1/S 150	150
L7	2No Stressline RW22A 140x215 dp PCC lintel (or similar) or 2No IG HD Box 140	150
All lintels to bear on full blocks		

- Builders Hole to Consolux details

- Notes:
- PRP have assumed the role of a Designer in the context of the Construction (Design and Management) Regulations and The Building Safety Act. All parties must be aware of their duties under this legislation.
 - Construction work shall not be started until designs have been approved by Building Control.
 - Do not scale from this drawing.
 - All dimensions are in millimetres unless noted otherwise. All levels in metres unless noted otherwise.
 - Drawing shall be read in conjunction with all relevant architect's drawings. The architect shall retain overall responsibility for dimensional control. Any inconsistencies shall be reported to PRP.
 - All levels and dimensions shall be checked on site before any work commences. Setting out remains the responsibility of others.
 - Buildings shall be constructed in accordance with Approved Document A of The Building Regulations. Drainage shall be constructed in accordance with Approved Document H of The Building Regulations.
 - Temporary works shall be designed by others to BS 5975
 - Fire protective measures shall be designed by the Architect or contractor in accordance with Approved Document B of the Building Regulations.
 - Waterproofing shall be designed by others in accordance with Approved Document C of the Building Regulations.
 - For more information see PRP drawings:
 - 64410 - 100series - Drainage and External Works
 - 64410 - 200series - Foundations
 - 64410 - 300series - Superstructure
 - This drawing must be read together with PRP drawings: 64410 - 300 - Typical Notes and Details

T2	21/11/2025	Issued for Tender	JD / HP
T1	14/11/2025	Amended to Arch comments Issued for Draft Tender	JD / HP
P3	04/11/2025	Connection markers added	JD / HP
P2	15/10/2025	Section markers added	JD / HP
P1	01/10/2025	Issued for comments	JD / HP
Rev	Date	Description	By / Chk


PRP
consulting engineers & surveyors

Spring Hill Office Park
Harborough Road
Pitsoford NN6 9AA

Telephone: 01604 889 870
northampton@prp.uk.com
www.prp.uk.com

Leicester
Northampton
London

engineering excellence | creating advantage

Client:	St Helens Pharmacy Ltd		
Architect:	Ascot Design		
Project:	33 Prestbury Road Wilmslow SK9 2LJ		
Title:	Superstructure Main House Second Floor Plan		
Status:	TENDER		
Engineer:	JKT	Date:	September 2025
Drawn:	KS	Scales @ A1:	
Checked:	HP		1:50
Project No:	64410	Drg No:	303
		Rev:	T2